AASHTO/FHWA RSA Peer Exchange

May 22-23, 2007 Charleston, SC

Rebecca Yao, P.E., PTOE

State Traffic Safety Engineer Wisconsin Department of Transportation




Agenda

- WisDOT Safety History
- WisDOT RSA History/Past Projects
- RSA Lessons Learned
- Current RSA Initiatives
- Current RSA Projects
- Future of RSAs in Wisconsin
- Questions



WisDOT Safety History

- 1990's: AASHTO NCHRP Projects
 - "Menu" of 22 Possible Safety Issue Areas
- 2000: Safety Summit
- 2001-2003: First Wisconsin SHSP
- 2005: SAFETEA-LU Requirements
 - Mandatory SHSP for Each State
 - 5% Lists
- 2005: Internal Update of SHSP for 2006-2008








WisDOT Safety History

2006-2008 SHSP Top 10 Issue Areas

- Increase Safety Belt Use
- 2. Improve Design/Operations of Intersections
- 3. Create a More Effective Safety Management System
- 4. Reduce Speed-Related Crashes
- 5. Reduce Impaired Drivers
- 6. Reduce Run off the road, Head-on and Median Crossover Crashes (Issue Areas 6, 8, 9)
- 7. Design Safer Work Zones
- 10. Increase Driver Safety Awareness





Existing Facilities

- FHWA Review of Wisconsin Bypass Road Design Practices
 - Analyzed four bypass segments in Wisconsin
 - Several improvements implemented
- US 151 Bypass (Fond du Lac) used access management to improve safety
- US 18/Bluemound Road
 - used access management to improve safety



Existing Facilities

- AAA Road Improvement Demonstration Program (RIDP) (on-going since 2004)
 - AAA funds high crash locations, often with HSIP funding
 - Recommends low-cost signing, marking, signal, and/or geometric improvements to reduce crashes
 - Audited > 50 intersections in Wisconsin







Design Stage


- Marquette Interchange
 - Mega project
 - RSA Performed at ~80-90% design completion





Design/Construction Stage

Burlington Bypass –
 additional intersection
 improvements
 implemented into design
 prior to construction







RSA Lessons Learned

- If RSAs are completed later in the design (60-90%), often hard to make changes
- If RSAs are completed earlier (planning or 0-30% design), not much detail provided
- RSA projects have helped reinforce traffic section recommendations
- RSAs provide flexibility at the regional and local levels, but yet provide consistency in documentation for statewide standards and policies




Current RSA Initiatives

- Master Contracts with two consulting firms
 - Developing RSA process for WisDOT
 - Pilot project(s) for RSA process
 - RSAs focusing on four areas of SHSP



- Value Engineering Road Assessment (VESA) Process Development
 - Incorporate RSA into VE process
 - Develop RSA parallel track to VE
 - RSA after VE









Current RSA Projects

Existing Facilities


 AAA Road Improvement Demonstration Program (RIDP)

- 4th Year Started in 2004
- Intersections with high crash rates
 in Milwaukee, Madison, and Green Bay
- US 8 Four-lane undivided rural highway through village
- Crash-Median Crossovers

Current RSA Projects

Design Stage

US 41 – Brown and Winnebago Counties



Future of RSAs in Wisconsin

- Develop Statewide RSA process/guidelines
 - Establish consistent RSAs within the state
 - Establish when to perform RSAs
 - Coordinate with value engineering
- Test RSA process with pilot projects (in accordance with SHSP issue areas)
- Incorporate RSA process into WisDOT policies and procedures



Future of RSAs in Wisconsin_(cont'd)

- Provide RSA training
- Establish annual RSA work plan
- Consider annual RSA project review process



Questions

Rebecca Yao, P.E., PTOE

State Traffic Safety Engineer

Wisconsin Department of Transportation 4802 Sheboygan Ave., Room 501 Madison, WI 53707 (608) 266-9381 rebecca.yao@dot.state.wi.us

