Curbing Wrong Way Movements onto Michigan's Freeways

Mark Bott, P.E. Engineer of Traffic & Safety Michigan DOT

Why the interest?



Study Details

Only included crashes caused by WRONG WAY ENTRY Onto the freeway system

Not included:

Crashes involving vehicle loss of control or Vehicles that crossed the median



Wrong Way Crash Severity

32% of crashes resulted in K or A-injuries (35 of 110)

Comparison: 2% of all freeway crashes result in K or A

The <u>35</u> KA crashes severely affected <u>66</u> people: 30 Fatalities 36 Incapacitating injuries

Severity by Location

Crash on an exit ramp 6% of crashes resulted in a K or A

Crash on freeway mainline 42% of crashes resulted in a K or A

By Location

Crash occurred on: exit ramp - (31) mainline - 71 - entry ramp unknown – 67 - entry ramp known (- 4) freeway-to-freeway ramp - 6 entrance ramp – 2


35 Known Entry Points

Lighting Conditions


78% occurred under conditions of darkness (86 crashes)

Question: Was there lighting at the ramp?? For 35 crashes with known entry point: 12 – daytime 15 – darkness, lighted 7 – darkness, unlighted 1 – dusk

By Time of Day



By Time of Day




Impaired Driving


(9 Crashes were drive-away – Impairment unknown)



60 Crashes, drivers were impaired: (54 of 60 at night)
48 under the influence of alcohol
7 under the influence of drugs
5 under the influence of both

By Age of Wrong Way Driver





Interchange Design


Can it affect wrong way crashes??

MDOT Interchange Types

791 Interchanges

35 Known Wrong Way Entries

Diamond – 340 Partial Cloverleaf – 163 Directional – 206 Full Cloverleaf – 20 Trumpet – 23 Other – 39




Partial Cloverleaf Interchanges





What do we already do?



From 8° angle between ramps to 11° angle.

From 30' setback to 20' setback for the corrugated island.

What else can we do?

LOW COST COUNTERMEASURES!

1. Lower Sign Height





2. Lollipops





3. Stop Bars & Placement



4. Off Ramp Wrong Way Arrow




5. Pavement Marking Extensions



6. Painted Island



7. Wrong Way Delineation



Potential Countermeasures:

- Lowering Signs to 4' Bottom Height
- Reflective Sheeting on Sign Posts
- Stop Bars
- Wrong Way Pavement Markings
- Turning Guidelines
- Painted Island
- Wrong Way Delineation on Ramp

Gratiot Ave @ I-94 (Detroit)




Gratiot Ave @ I-94

"Video taken at the interchange indicates that drivers may be staying to the left of the barrier because they cannot see the on-ramp on the barrier's other side." Wash DOT, 2001

Public Roads, Sep/Oct 2002

Gratiot Ave @ I-94 Improvements




- Qwick Kurb
- Lower Signs
- Pavement Markings

Gratiot Ave @ I-94 Results

ZERO wrong way crashes since June 2012

 No winter maintenance issues with Qwick Kurb

Wrong Way Detection I-94 at Sargent Road




I-94 at Sargent Road


Pavement marking and signing changes completed in Fall 2017 to reduce driver confusion



I-94 at Sargent Road



- Location 1 & 2: 36" Wrong Way Sign w/red flasher ring
- Locations 3, 5, 6: 48" Wrong Way Sign w/red flasher ring
- Location 4: 48" Wrong Way Sign w/red flasher ring and controller



I-94 at Sargent Road

